

BOQ for the work: "CONSTRUCTION OF BOUNDARY WALL, RAZOR WIRES & WATCH TOWER ETC AT ISLAMIA COLLEGE PESHAWAR"					
			Approx: Cost Rs. 2910494		
			2% Earnest Money Rs. 58210		
			Date of Opening: 14-03-2017		
S.No	Description of items		MRS-2016 Cost (Rs)	Percentage Above/ Below/ At-par	Total Amount (Rs)
A: S.H: All MRS-2016 Qtr-1 Items:					
1	S.H:	CIVIL WORKS	2655962	_____% Above/ Below/ At-par	
2	S.H:	INTERNAL ELECTRIFICATION	20889	_____% Above/ Below/ At-par	
3	S.H:	WATER SUPPLY & SANITARY	111441	_____% Above/ Below/ At-par	
Total Quoted Cost of Sub Head: (A) Rs.					
B: S.H: Non-MRS Items:			Quantity	Quoted Rate	Amount (Rs)
1	Providing & fixing razor wire fixed with 2Nos steel wire 10 gauge, 2ft dia bundles @ 20ft per 10kgs including angle iron (Y-shaped) 1.5"x1.5"x3/16" commercial size fixing on walls with PCC (1:2:4) complete.		365 Rft	
2	P/Making manhole of 4.5" thick B.B. masonry having 2'x2' internal size i/c bed (1:4:8), plaster without cover complete		4 Nos	
Total Quoted Cost of Sub Head: (B) Rs.					
Total Quoted Cost of Sub Head: (A) & (B) Rs.					
Note: All other/ extra items if required on site will be paid on MRS-2016 (Qtr-1) on same approved premium or market rate analysis.					

Director of Works,ICP

Sub-Engineer,ICP

Signature of Contractor